



Corrigendum No.4 to the Tender Dossier
Supply of equipment for the development of hydrological flood forecasting system for Sava River
Basin in Bosnia and Herzegovina (Phase 1, Bosna River)

Publication reference: EuropeAid/138452/SUP/BA; Tender no: EC/BIH/16/018

The Tender Dossier is corrected as follows:

ANNEX II + III: TECHNICAL SPECIFICATIONS + TECHNICAL OFFER

➤ **LOT 1: IT and Supporting Equipment**

Item 1.2. DATABASE SERVER – 6 pcs

In the requirement: "Internal Storage: • min. 2 TB internal storage (hot pluggable HDD);" the following text is added:

"SATA, SAS or SSD, at least 10K, RAID 1"

➤ **LOT 4 – Meteorological and Hydrological Stations**

Item 4.1. Precipitation gauge station - 11 pcs

a) The requirement: "Communication interfaces: USB host and USB device, RS-232." is deleted and now reads:

*"Communication interfaces: USB host and USB device **and/or** RS-232."*

b) In the requirement: "All-weather precipitation gauge sensor that uses superior weight-based technology to measure the amount and intensity of rain, snow, and hail."

- the following point: "• Accuracy: max.. ± 0.1 %;" is deleted and now reads:

"• Accuracy: max.. ± 1 %;"

- the following point: "• Interface: SDI-12 or RS-485." is deleted and now reads:

"• Interface: SDI-12, RS-485."

c) In the requirement: "The digital weather sensor reliably measures the relative humidity and temperature."

the following point: "• Accuracy TRH: max. ± 3 % , RH max. ± 0.5 °C;" is deleted and now reads:

"• Accuracy for Temperature max. $\pm 0,5$ °C and for RH max. ± 3 %".

Item 4.2. Complex Meteorological station - 9 pcs

a) In the requirement: "Control cabinet characteristics:" the following point:

"• Communication interfaces: USB host and USB device, RS-232;" is deleted and now reads:

*"• Communication interfaces: USB host and USB device **and/or** RS-232."*

b) In the requirement: "All-weather precipitation gauge that uses superior weight-based technology to measure the amount and intensity of rain, snow, and hail."

the following point: "• Accuracy (precipitation): up to ± 0.1 %" is deleted and now reads:

"• Accuracy (precipitation): up to ± 1 %;"

Item 4.3. Groundwater Level Measuring Station – 3 pcs

The following requirement is added:

"Cable length for groundwater level measuring station should be 40 m."

These changes apply to the whole tender dossier. All other terms and conditions of the Tender Dossier remain unchanged. The above changes to the Tender Dossier are integral part of the Tender Dossier.